



Seaworthy Condition Report

Seaworthy Condition Reference Number SCR #.	SCR1951
Location SCI	Busselton
Date of SCI	05/04/2024
Reason For Survey	Pre-Purchase Inspection
Type of Survey	Engine and electrics only.
Technician	Leon
Prepared For	Ian Crosby
Inspection Address	Onsite
Vessel Type	Power Boat/ Trailer
Vessel Name	N/A
Vessel Year	2006
Vessel Make and Model	Sea Ray
Vessel Hull Identification Number (HIN)	ISO1221714946
Vessel Registration Number	D0265
Vessel Length Overall (Loa)	
Engine Year	2006
Engine Make and Model	Mercurius 6.2L MPI
Port/Main Engine Serial Number	OW664725
Starboard Engine Serial Number	N/A
Engine Hours Port/Main	185hrs
Engine Hrs Stb.	N/A



Boat/Vessel

Hull	GRP
Floor/Deck	GOOD
Transom	GOOD
Electronics - Corrosion Damage	GOOD
Battery condition	GOOD CONDITION
Battery Tie Down Box	SECURE
Fuel Tanks & Restraint	GOOD
Fuel Lines & Filters	GOOD/ FUEL COOLER WATER LEAK from fitting.
Engine Instruments	WORKING
Dash Lighting	WORKING
Navigation Lights	PORT/STARBOARD WORKING. ANCHOR LIGHT NOT WORKING
General Lighting	WORKING.
Wiring & Fuses	GOOD
Windscreen/Wipers	N/A
Mooring Ropes/Lines/Cleats	N/A
Bilge Pump & Float-Switch Operations	WORKING
Horns	NOT WORKING
Electronics	TRIM TAB STARBOARD NOT WORKING, FLUID LOW.
Sea Cocks & Valves	WATER LEAKS FROM SEA STRAINER LID AND HULL FITTINGS
Doors & Latches	GOOD
Engine	
Engine Condition	GOOD, LOW HOURS ON ENGINE, SOME WATER LEAKS AS DETAILED
Engine Oil Visual	GOOD CONDITION
Drive Oil Remote Bottle Level	GOOD CONDITION
Engine Battery Cables	GOOD CONDITION
Switches & Terminals	GOOD CONDITION.
Gearbox Operation	GEARS WORKING SHIFTS SMOOTHLY
Gear Oil Condition	GOOD
Power Trim Oil	GOOD FULL
Engine Control Operation	GOOD
Engine Electrical Harness	GOOD CONDITION
Charging System	ENGINE IS CHARGING, LOAD TEST ON BATTERY'S ALL OK
Anode Condition	GOOD
Starting Mechanism	WORKING



Fuel Filters	GOOD NO LEAKS
Trim/Tilt Operation	OPERATIONAL,
Propellor Condition	GOOD, SLIGHT DAMAGE TO SKEG
Engine Mounting Bolts	GOOD
Visual Inspection for Water Ingress	NIL AROUND TRANSOM AREA, SIGNS OF WATER ON MANIFOLDS
Engine Cooling System	NEEDS ATTENTION WATER LEAKS
Battery	LOAD TESTED OK
Air Filters & Frame Arresters	GOOD, CLEAN
DTC Codes	NO FAULTS PRESENT
Safety	
Life Jackets	
Anchor	
Electric Winch Operation	
Oars & Paddles	
Flares In Date	
Fire Extinguisher	
Distress Beacon	
Trailer	
Wheels	
Wheel Bearings	
Tyres	
Winch	
Cable & Hook	
Coupling-Ball Weight	
Lights	
Boat Roller	
Bunker Condition	
Alignment	
Safety Chain	
Rated Shackles	
Trailer General Condition	
Brakes	
CONCLUSION COMMENTS AND RECOMMENDATIONS	
Overall condition very good, few minor issues.	
Compression Test 1. 135psi, 2. 135psi, 3. 130 psi, 4. 145 psi, 5. 130psi, 6. 130 psi, 7. 140 psi, 8. 140 psi.	
Fault diagnosis on anchor light.	
Repair water leaks Sea strainer and fuel cooler, may need skin fitting resealed.	
Top up trim tab fluid and retest.	
Oil samples taken and sent away, may take 2 weeks to get back.	


